

SYNTHETIC TRAINING DATA - NOT A REAL PROJECT OR ISSUED TENDER  
BAKU COMMERCIAL CENTER - TECHNICAL SPECIFICATION REVISION B  
Tender package: BCC-2026-041 | Issue date: 14 September 2026  
Prepared for software testing only. All project details and quantities are fictional.

SECTION 03 30 00 - CAST-IN-PLACE CONCRETE

Concrete for structural slabs and columns: strength class C30/37.  
Estimated volume: 860 m3. Reinforcement: B500B, estimated 142 tonnes.  
Concrete shall be supplied with batch tickets and test certificates.

SECTION 05 12 00 - STRUCTURAL STEEL

Secondary hot-rolled steel framing: grade S355JR, estimated 38 tonnes.  
Protect exposed steelwork with the approved corrosion protection system.

BAKU COMMERCIAL CENTER - TECHNICAL SPECIFICATION REVISION B (continued)

SECTION 07 21 00 - THERMAL INSULATION

External-wall mineral wool: density not less than 100 kg/m<sup>3</sup>.

Required thickness: 150 mm. Estimated area: 4,500 m<sup>2</sup>.

SECTION 07 52 00 - ROOF WATERPROOFING

Provide a two-layer SBS modified bitumen membrane system.

Measured roof area: 1,850 m<sup>2</sup>. Include compatible primer and laps.

SECTION 09 30 00 - FLOOR FINISHES

Finish FF-02: porcelain floor tile, 600 x 600 mm, slip rating R10.

Revision B baseline area: 4,700 m<sup>2</sup>, subject to later written revisions.

BAKU COMMERCIAL CENTER - TECHNICAL SPECIFICATION REVISION B (continued)

SECTION 26 05 13 - LOW-VOLTAGE CONDUCTORS

Emergency lighting and fire alarm circuits require FE180/PH120 fire-rated cable, 3 x 2.5 mm<sup>2</sup>. Estimated route length: approximately 550 m.

General power cable is not an acceptable substitute for these circuits.

SECTION 33 31 00 - SITE DRAINAGE

Underground drainage: HDPE PE100 pipe, DN110, SDR17.

Current coordinated quantity: 1,550 m, subject to Revision C-02.

END OF SYNTHETIC TECHNICAL SPECIFICATION